

**Glasswall NR (Non-reinforced)
Resinous Wall System****Part 1 - GENERAL****1.01 RELATED DOCUMENTS**

- A. Drawings and general provisions of Contract, including General and Supplemental Conditions and Division 1 Specification sections apply to work of this Section.

1.02 WORK INCLUDED

- A. Provide materials, labor and equipment required to prepare designated ceiling area and install coating system as shown on the drawings.
- B. Related Work:
1. Section 03300: Concrete Work, for concrete substrate.
 2. Section : Plumbing, drains.
 3. Section 07000: Sealants, silicone sanitary and USDA sealants.

1.03 QUALITY ASSURANCE

- A. Manufacturer: Obtain all ceiling system materials required for this Section from a single manufacture.
- B. Contractor: Shall have a minimum of 10 years experience in the installation of 100% solids epoxy coating systems. Shall be Approved Installer of Manufacturer specified.

1.04 SUBMITTALS

- A. Manufacturer's data for ceiling system, including the following:
1. Physical Properties
 2. Performance Properties
 3. Material Safety Data Sheets
- B. Manufacturer's standard single source warranty in accordance with Section 1.05 WARRANTY.
- C. Contractor Experience: Select a contractor with a minimum of 10 years experience installing the specified system and with written certification from the Manufacturer.
- D. Manufacturer's standard color charts for color selection.
- E. Three 12" X 12" system samples for purposes of chemical resistance testing and finish texture approval.

1.05 WARRANTY

- A. Furnish manufacturer's written warranty on seamless ceilings, for period of two years after installation., warranting against loss of bond and wear through to concrete substrate (through normal wear and use). Warrant shall be single source from the manufacturer, including material and labor.

LSP Performance Resins Technical Specifications
Glasswall NR (Non-reinforced) Resinous Wall System

1.06 DELIVERY, HANDLING AND STORAGE

- A. Deliver materials in manufacturer's unopened, undamaged containers, clearly marked with the following:
 - 1. Product Name
 - 2. Manufacturer's Name
 - 3. Resin or Hardener Designation
 - 4. Mix Ratio of Resin and Hardener
- B. Handle materials in a safe and proper manner to avoid damage or spills.
- C. Inspect direct job site deliveries to verify correct material and quantities are received in good condition.
- D. Replace, at no cost to the owner, materials that are found to be defective in manufacturing or damaged in transit, handling or storage.
- E. Store materials per manufacturer's instructions and as follows:
 - 1. Seals and labels shall be intact and legible.
 - 2. Temperature of storage area shall be maintained between 60°F and 85°F.
 - 3. Do not use materials which have been stored for a longer period of time than the manufacturer's maximum recommended shelf life.

1.07 JOB SITE CONDITIONS

- A. Pre-Installation conference shall be required with General Contractor, Owners Representative, Seamless Contractor and/or Manufacturer's Representative to review the following:
 - 1. Evaluate substrate conditions and extent of repairs necessary for Contractor to begin normal preparation and installation of seamless ceiling finishes.
 - 2. Evaluate detail conditions at all penetrations, terminations and perimeter locations. Detail problems should be documented and resolved prior to beginning coatings.
 - 3. Test wall substrates to verify that they are sound and "fit" for coating according to manufacturer and bid documents.
 - 4. Review job site conditions, including temperature, power, and lighting, necessary for a successful installation.
- B. Protect surrounding substrate and surfaces, as well as in place equipment, from damage during surface preparation and system installation.
- C. Job area shall be free of other trades during wall installation, and for a period of 48 hours upon completion.
- D. General Contractor shall provide adequate ventilation by use of fans or other devices.
- E. General Contractor shall maintain lighting at a minimum uniform level equivalent to the end use conditions in the areas where the seamless wall system is being installed. If possible, schedule installation so that permanent lighting will be operational during installation.
- F. General contractor shall ensure that leaks from pipes and other sources are corrected prior to wall installation.
- G. General Contractor shall provide minimum substrate temperatures of 65 degrees F and atmospheric temperature of 70 degrees F with relative humidity below 85% during wall installation and until final acceptance.

LSP Performance Resins Technical Specifications
Glasswall NR (Non-reinforced) Resinous Wall System

1.08 CURING, CLEAN UP AND PROTECTION

- A. Cure final wall system in accordance with manufacturer's recommendations. Cure time shall be a minimum of 48 hours prior to traffic and 7 days before exposure to chemicals.
- B. Clean up work area, removing all equipment, materials and trash.
- C. General contractor shall provide temporary protection from construction traffic and other trades prior to final acceptance by the owner.

Part 2 - Products

2.01 Materials

A. Ceiling Systems Overview

The ceiling system specified shall be SeamTek GlassWall NR by Life Science Products. This system is a high build epoxy finish applied in a minimum thickness of 12-16 mls Dry Film Thickness (DFT). The system shall be pinhole free. Use 100% solids epoxy resins, no solvent containing materials will be allowed.

Epoxy Physical Properties For GlassWall NR

Hardness Shore D	ASTM D-1706	70 - 80
Tensile Strength	ASTM D-638	3,000 psi min.
Flexural Strength	ASTM D-790	4,000 psi min.
Thermal Shock	Mil F-52505	No cracking or loss of adhesion
Abrasion Resistance (Taber Abrader, CS-17 Wheels, 1000 gm. load, 1000 cycles)	ASTM D-4060	.035 gm loss
Ultimate Elongation	ASTM D-638	20% min.
Chemical Resistance	20% Acetic Acid	Occasional Spill
	50% Citric Acid	Good
	20% Nitric Acid	Occasional Spill
	30% Hydrochloric Acid	Occasional Spill
	10% Hydrofluoric Acid	Occasional Spill
	Hydrogen Peroxide	Good
	40% Potassium Hydroxide	Good
	40% Sodium Hydroxide	Good
	50% Sulfuric Acid	Good
	Urea	Good

LSP Performance Resins Technical Specifications
Glasswall NR (Non-reinforced) Resinous Wall System

Part 3 - Execution

3.01 Surface Preparation

- A. Existing drywall surfaces shall be sanded and wiped clean prior to installation of coating system. New drywall joints shall be taped and prepared to receive system. In short, new construction shall be paint ready.

3.02 APPLICATION

- A. Apply each component of system per manufacturer's installation instructions, including mixing and application.
- B. Cure resinous wall system materials in compliance with manufacturer's directions.

3.03 CLEANING AND PROTECTION

- A. Cleaning: Remove all debris resulting from the wall installation during the progress of the work.
- B. Protection: General contractor shall provide protection from other trades prior to final acceptance by owner.